#### United States Department of the Interior National Park Service

## **National Register of Historic Places Registration Form**

CA 538

This form is for use in nominating or requesting determination for individual properties and districts. See instructions in *How to Complete the National Register of Historic Places Registration Form* (National Register Bulletin 16A). Complete each item by marking "x" in the appropriate box or by entering the information requested. If an item does not apply to the property being documented, enter "N/A" for "not applicable." For functions, architectural classification, materials, and area of significance, enter only categories and subcategories from the instructions. Place additional entries and narrative items on continuation sheets (NPS Form 10-900A). Use typewriter, word processor or computer to complete all items.

1. Name of Property		
historic name Coastie Head Lookout Cabin		
other name/site number Starbuck Creek Cabin		
2. Location		
street & number Approximately 2.4 miles south of Norv Mora Sub-district	vegian Memorial:	not for publication
city or town Olympic National Park Headquarters, Por	t Angeles	vicinity
	nty <u>Clallam</u> code <u>009</u>	zip code <u>98362</u>
3. State/Federal Agency Certification		
As the designated authority under the National Historic Preservation Adeligibility meets the documentation standards for registering properties requirements set forth in 36 CFR Part 60. In my opinion, the property property be considered significantnationallystatewide	in the National Register of Historic meetsdoes not meet the	Places and meets the procedural and professional ne National Register criteria. I recommend that this
Signature of certifying official/Title	Date	
In my opinion, the property Adoes not meet the l	Jational Register criteria ( S	See continuation sheet for additional comments.)
miny opinion, the project of the contract th	7-/1	1/07
Signature of certifying official/Title	Date	-
	esosic Prisem	uanes struct
State of Federal agency and bureau		
4. National Park Service Certification		
I hereby certify that the property is:	Signature of the Keeper	Date of Action
entered in the National Register.		
——— See continuation sheet.  determined eligible for the National Register.  ———— See continuation Sheet.		
determined not eligible for the National Register.		
removed from the National Register.		
other, (explain:)		



Clallam County, WA County and State

5. Classification				
Ownership of Property (Check as many boxes as apply)	Category of Property (Check only one box)		urces within Property usly listed resources in the count.)	
private	x building(s)	Contributing	Noncontributing	
public-local	☐ district	1	t	ouildings
public-State	☐ site			sites
x public-Federal	structure		st	tructures
	Object		o	bjects
		1	Т	Cotal .
Historic Resources of Olympic ?  6. Function or Use	National Park			
Historic Functions		Current Functions		. =.
(Enter categories from instructions)		Enter categories from instruction	ons)	
Coast Guard Cabin		Shelter / Vacant		
7. Description				
Architectural Classificati	<del></del>	Materials		
(Enter categories from instructions)	•	(Enter categories from instruct	ions)	
OTHER: Vernacular	•	foundation Post and P walls Wood Boa roof Wood Sha	<u>rd</u>	
		roof <u>Wood Sha</u> other <u>Wood</u>	<u>«c</u>	

**Narrative Description** 


(Describe the historic and current condition of the property on one or more continuation sheets.)

Summary: The Coastie Head Lookout Cabin is a small, simple, rectangular, 1-story, wood-frame building with a wood-shaked gable roof set on a post and pier foundation. It is located on the bluff of a promontory known as Coastie Head, south of Starbuck Creek. There is no description in the Coast Guard files of a coastal lookout station being constructed at Coastie Head; however, it is very possible that this structure was built by the Coast Guardsmen during World War II as part of the Northwest Sea Frontier Coastal Lookout System, circa 1942. The Coastie Head Lookout Cabin may have been built as a temporary structure and not included in the official record. The building is in fair condition and retains integrity of location, setting, design, materials, workmanship, feeling, and association.

8. 5	Statement of Significance		
(Mar	chicable National Register Criteria  k "x" in one or more boxes for the criteria qualifying the property  lational Register listing.)		Areas of Significance (Enter categories from instructions)
П	<ul> <li>A Property is associated with events that have made a significant contribution to the broad patterns of our history.</li> <li>B Property is associated with the lives of persons significant in our past.</li> </ul>		Criterion A: Politics/Government
	<ul> <li>C Property embodies the distinctive characteristics of a type, period or method of construction or represents the work of a master, or possesses high artistic values, or represents a significant and distinguishable entity whose components lack individual distinction.</li> <li>D Property has yielded, or is likely to yield, information important in prehistory or history.</li> </ul>		Period of Significance 1942 - 1943
(Mar	teria Considerations k "x" in all the boxes that apply.) Property is:		Significant Dates  1942
	<ul> <li>A owned by a religious institution or used for religious purposes.</li> <li>B removed from its original location.</li> </ul>		Significant Person (Complete if Criterion B is marked above.)
	C a birthplace or grave		Cultural Affiliation
	<ul> <li>D a cemetery.</li> <li>E a reconstructed building, object, or structure.</li> <li>F a commemorative property.</li> </ul>		Architect/Builder
∐ Na:	G less than 50 years of age or achieved significance within the past 50 years.  rrative Statement of Significance olain the significance of the property on one or more continuation sheets.)		United States Coast Guard
	Major Bibliographical References		
(Cite	bliography the books, articles, and other sources used in preparing this form on one or more Previous documentation on file (NPS): preliminary determination of individual listing (36 CFR 67)	conti	nuation sheets.)  Primary location of additional data:  State Historic Preservation Office
	previously listed in the National Register		Other State Agency
	previously determined eligible by the National Register	х	Federal agency
Ш	designated a National Historic Landmark		Local government
	recorded by Historic American Buildings Survey #		University
	recorded by Historic American Engineering Record #	∐ Nai	Other ne of Repository:

city or town





### 10. Geographical Data Acreage of Property: Less then one acre **UTM References** (Place additional UTM references on a continuation sheet.) 3 5318125 1 10 374807 easting northing zone 4 2 See continuation sheet **Verbal Boundary Description** The boundary is formed by lines completing a rectangle 100 feet from the four sides of the building. **Boundary Justification** The building includes the cabin plus the coastal vista to the west (which is significant to the cabin's location as a W. W. II Lookout) and the forest setting. 11. Form Prepared By name/title Gail E.H. Evans, Historian / Stephanie Toothman, Regional Historian (1986), Gretchen Luxenberg, Historian (1998), and Jacilee Wray, Anthropologist (2005). organization National Park Service, Columbia Cascade Support Office date 1986/1998 telephone (206) 220-4138 street & number 909 1st Avenue city or town Seattle State Washington zip code <u>98104-1060</u> Additional Documentation Submit the following items with the completed form: **Continuation Sheets** Maps A 7.5 minute USGS map indicating the property's location. A sketch map for historic districts and properties having large acreage or numerous resources. **Photographs** Representative black and white photographs of the property. **Additional Items** (Check with the SHPO or FPO for any additional items.) **Property Owner** (Complete this item at the request of SHPO or FPO.) name street & number telephone

Paperwork Reduction Act Statement: This information is being collected for applications to the National Register of Historic Places to nominate properties for listing or determine eligibility for listing, to list properties, and to amend existing listings. Response to this request is required to obtain a benefit in accordance with the National Historic Preservation Act, as amended (16 U.S.C. 470 et seq.).

state

zip code

Estimated Burden Statement: Public reporting burden for this form is estimated to average 18.1 hours per response including time for reviewing instructions, gathering and maintaining data, and completing and reviewing the form. Direct comments regarding this burden estimate or any aspect of this form to the Chief, Administrative Services Division, National Park Service, P.O. Box 37127, Washington, DC 20013-7127; and the Office of Management and Budget, Paperwork Reductions Projects (1024-0018), Washington, DC 20503.

#### United States Department of the Interior National Park Service

# National Register of Historic Places

### Continuation Sheet

Section number 7 Coastie Head Lookout Cabin: Clallam County, WA Page 1

Narrative Description: The existing Coastie Head Lookout Cabin is located on top of the promontory known as Coastie Head. There is no description in the Coast Guard files of a coastal lookout station being constructed at Coastie Head; however, it is possible that this structure was built by the Coast Guardsmen during World War II as part of the Northwest Sea Frontier Coastal Lookout System, circa 1942. The Coastie Head Lookout Cabin may have been built as a temporary structure after the lookouts identified in the official record were completed. After the war, the structure was used as a hiker's shelter by those who knew its location or happened upon it.

The structure is rectangular in shape, measuring about 8' x 10' with a 4' porch off its west elevation. It is 1-story, built of wood-frame construction, and set on a post and pier foundation. Some of the vertical side wall boards may have been collected off the beach. The gable roof is sheathed with a combination of wood shakes and roofing paper over boards. A shed roof porch is also covered with roofing paper over boards and is supported by milled 2 x 4s. The main elevation has an off-center wooden door made of horizontal boards with bracing and a window opening. There are two window openings (no sash) with simple wood trim. The cabin appears to have been the recipient of mostly in-kind repairs over the years. Other windows appear to have been closed off with the addition of boards, at least on the rear elevation.

The building was in poor condition in June of 2002, when Boy Scout Troup 66 member Evan Miller and his family made repairs to the wall support beam, outer walls, flooring, and bench, and prepared interpretive information that is retained in a binder inside the structure. The building continues to exhibit the characteristics and qualities of its historical appearance, which were probably just as primitive; therefore, it retains integrity of location, setting, design, materials, workmanship, feeling, and association. It exhibits the registration requirements identified in the Multiple Property Documentation form for the Historic Resources of Olympic National Park.

#### SEE ATTACHED INVENTORY CARD PREPARED IN 1982 FOR PROPERTY.

#### Statement of Significance:

Summary: The Coastie Head Lookout Cabin is significant for its association with politics and government activities within what is today Olympic National Park (criterion A). This building is believed to be the only known coastal lookout station associated with World War II military defense efforts that still exists along the 62-mile coastline of Olympic National Park, and possibly on the peninsula. The cabin is indicative of a property type identified in the Multiple Property Documentation form for the Historic Resources of Olympic National Park: Government. It retains integrity in its location, setting, design, workmanship, materials, feeling, and association, and meets the registration requirements set forth for these properties in the Multiple Property Documentation form.

Narrative: The surprise attack on Pearl Harbor in the Hawaiian Islands by the Japanese on December 7, 1941, thrust the United States into World War II. Japan's attack immediately spawned rumors and fears of a Japanese invasion of the western shores of the United States. The U.S. hastily organized air, ground, and sea defenses to protect the West Coast against any such surprise attacks by the Japanese.

#### United States Department of the Interior National Park Service

# National Register of Historic Places Continuation Sheet

Section number 8

Coastie Head Lookout Cabin: Clallam County, WA

Page 2

Many military personnel considered the Olympic Peninsula one of the most threatened and vulnerable parts of the contiguous United States. Forming the southern edge of the Strait of Juan de Fuca, the Olympic Peninsula is at the entrance to one of two principal inland waterways extending from the Pacific Ocean to strategically important northwest coastal cities. It was believed that the peninsula would be the first to feel the effects of an attack from an alien country approaching the U.S. from the west.

This defense patrol system was instituted in the Atlantic, Gulf, and along the entire Pacific coastline. The threefold purpose of the system was to prevent communication between persons on shore and the enemy; to observe the actions of any enemy vessels in coastal waters and to transmit such information to Naval or Army commands; and finally, to report attempts of enemy landing to Army and Naval commands and to assist in preventing such action. The United States Coast Guard played an important role in what became known as the Coastal Lookout System, as they carried out the Navy's operations to gain and command the vital sea area. The Navy supported the Army, who was ultimately responsible for beach defense.

The Port Angeles sector of the lookout system, extending from Cape Flattery south to Cape Elizabeth, a distance of about 65 miles, presented some of the greatest physical obstacles found anywhere in the country for establishing a defense system. The thick forests, nearly impenetrable underbrush, and steep, rocky bluffs along the coastline all contributed to the difficulties the Coast Guard had in establishing key strategic points.

One of the first moves by the 13th Naval District in the Port Angeles sector was to take over the Army camp and patrols at the north end of Ozette Lake. The coast guardsmen departed Seattle on September 1, 1942, and when they arrived at the lake the Army departed. By the following morning, two primitive tent camps on the beach had been established about three miles from the lake. Within two weeks, tents were located at five beach camps, and trails were opened through the dense forests between the coast and the 9½ mile-long Ozette Lake. At the height of Coast Guard activity in the Ozette Lake area, ten beach patrol outposts and three coastal lookout towers were in operation. Spaced at regular intervals between Shi Shi Beach and Cape Johnson, the beach patrol outposts were at Seafield, Cape Alava, Sand Point, Wink Trail, Yellow Banks, Township Trail, Allen Trail, Lone Tree Rock, and Cape Johnson. The three lookout "towers" were at Cape Alava on Cannonball Island, Eagle Point on Lake Ozette, and Starbuck, just north of Cedar Creek (the Coastie Head Lookout lies further south down the coast, but is often misnamed Starbuck Lookout).

Material used to build these cabins was transported by raft from Neah Bay or packed in by guardsmen. Trails either along the beach or through the woods, telephone lines, and fixed or portable radios facilitated communication between the beach patrol outposts, the lookouts, and the patrol station at Ozette Lake.

The activity of the beach patrol units in the Ozette Lake area was short lived. By the summer of 1943 the danger of enemy landings on the west coast declined and the number of military personnel stationed along the coastline was severely reduced. The Ozette Lake Coast Guard encampment was decommissioned on March 29, 1944. Little evidence remains of the presence of the Coast Guard in the Ozette Lake area. The Coastie Head Lookout cabin is the only structure remaining that could be associated with the patrol operations.



# National Register of Historic Places Continuation Sheet

Gail Evans identified this structure as the Starbuck Creek Lookout Cabin. However based on Coast Guard files the Starbuck Creek Lookout Cabin was located in Section 18, T29N, R15W, just above Cedar Creek. Archer Smith visited the site soon after WW II and wrote in his book that the top of the pinnacle upon which it was built collapsed and the structure was destroyed (Smith 1997:44). The existing Coastie Head Lookout Cabin is located one section south of the Starbuck lookout site, in Section 19, T29N, R15W, on top of the promontory known as Coastie Head, to the north of Saddle Point. There is no description in the Coast Guard files of a coastal lookout station being constructed at Coastie Head; however, it is possible that this structure was built by the Coast Guardsmen during World War II as part of the Northwest Sea Frontier Coastal Lookout System, circa 1942. The Coastie Head Lookout Cabin may have been built as a temporary structure and not included in the official record. Interviews with Lester Anthis, a beach patrolman along this stretch of coastline from spring 1942 until fall 1943, suggest this cabin was already built when the Coast Guard arrived and may have had some connection to the dredging operations at Starbuck. Even if this is the case, the structure is commonly believed to be a coastal watch station, as the headland's name, "Coastie Head," suggests.

The Coastie Head Lookout cabin is significant for its association with the United States government's efforts and activities to protect the west coast of the Olympic Peninsula from enemy attack during World War II; in what today is Olympic National Park (criterion A). This building is noteworthy in that it appears to be the only extant structure from the coastal lookout defense system that remains along the peninsula since this significant era in U.S. history. It is a functional building with a specific purpose, and its design and method of construction reflect this purpose and function. The use of natural materials applied in a simple, straightforward manner is representative of the speed in which these buildings were erected on behalf of the war effort. It is an example of a property type identified in the Multiple Property Documentation form for the Historic Resources of Olympic National Park: Government. It retains integrity in its location, setting, design, materials, workmanship, feeling, and association, and meets the registration requirements set forth in the Multiple Property Documentation form.

#### Bibliography:

Anthis, Lester, personal communication, January 27, 2005 Evans, Gail. Historic Resource Study. NPS. 1983. Smith, Archer K. Tragedy Graveyard, the Starbuck Ghost and Other True Stories, 1997

<b>6/82</b>	
7-100 001-F	
Z	

PNR-100 6/82		National Park Service Westin Building, Devitic Northwest Peoion 2001 Sixth Ave	5, 3
1. SITE LD. NO	INVENTORY	Cultural Resources Division	, E
2 NAME(S) OF STRUCTURE (2032)	5. ORIGINAL USE	7. CLASSIFICATION	
STARBUCK CREEK LOOKOUT CABIN	Coast Guard		1
	Cabin		
3. SITE ADDRESS (STREET & NO)	8. PRESENT USE		
Approx. 3.8 miles from Allen's Bay Trailhead	Unoccupied		7
on Ozette Lake		8. UTM ZONE EASTING NORTHING	
		10 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	0
4. CITY/VICINITY COUNTY	STATE	SCALE 1:24 ( 1:62.5 ) OHAD 0.00 + + 0	
Approx. 6 miles south of Ozette R.D., Clallam, Washington	Washington	OTHER. NAME	ب
12. OWNER/ADMIN ADDRESS			

c. 1942

10. DATE

11, REGION PNR

Room 1920

ton 98121 9. RATING

June 1942, the coastal lookout system, consisting of a series of lookout stations, lifeboat stations, and beach patrols, the fall of 1942, the Port Angeles sector of the 13th Naval District established a Coast Guard station at the north end of Ozette Lake, one mile inland from the Pacific coast. Soon after their arrival at Ozette Lake, guardsmen established was substantially complete. For organizational purposes the entire Northwest coastline was divided into sectors. In ten beach patrol outposts and three coastal lookout "towers" located at regular intervals along the coast between Shi The Starbuck Creek Lookout Cabin was constructed by the U.S. Coast Guard during World War II as part of the Northwest Frontier coastal lookout system. This defense patrol system, which was instituted in the Atlantic Gulf and along Department of the Interior, National Park Service, Olympic National Park, 600 East Park Ave., Port Angeles, WA 98362 the entire Pacific coastline, was established to prevent enemy (primarily by the Japanese)land, or air invasion. 13. DESCRIPTION AND BACKGROUND HISTORY INCLUDING CONSTRUCTION DATE(S), PHYSICAL DIMENSIONS, MATERIALS, MAJOR ALTERATIONS, EXTANT EQUIPMENT, AND IMPORTANT BUILDERS, ARCHITECTS, ENGINEERS, ETC.

Shi Beach and Cape Johnson. The cabin near the mouth of Starbuck Creek is believed to be one of the three "lookout towers"

for the purchase of fifty miles of coastal land, including the Starbuck Creek area. In 1953, this entire coastal strip was added to Olympic National Park. At various times since World War II, the Starbuck Creek Lookout Cabin was probably

in the Ozette Lake section of the coastal lookout system. In 1940 Public Works Administration monies were authorized

used by the Park Service as quarters for seasonal employees. Within the coastal strip of Olympic National Park, this

structure is the only known cabin associated with the World War II beach patrol that is still in existence.

Rectangular in shape; measures approx. 8' x 10' with 4' porch off west elevation; 1 story; wood-frame wall construction UNKNOWN Detectoration 15. DANGER OF DEMOLITION? SPECIFY THREAT) RUINS S DETERIORATED 0000 C EXCELLENT

with board siding, probably from beach; gable roof with wood shakes; post and pier foundation; window cut into wall with no trim; no door; interior board floor. Alterations: board siding has been replaced through time. Siting: on bluff overlooking Washington coastline. жжжжжжж (Item No. 13 continued) 16.SIGNIFICANCE

States during World War II. It is the only known coastal lookout station associated with the World War II U.S. military defense effort that is still in existence along the 50 mile coastal strip of Olympic National Park and, possibly, the Olympic Peninsula. It is an example of a property type -"Government"—and has Starbuck Creek Lookout Cabin, circa 1942, is significant under Criterion A for its association with the coastal lookout system on the west coast of the United integrity for listing in the National Register.

Bickestol R

NATIONAL WILDLI

T.29N., R. 15W., SEC.19,

W.M.

19. PUBLIC ACCESSIBILITY 18. LOCATED IN AN HISTORIC DISTRICT? 21. REFERENCES—HISTORICAL REFERENCES, PERSONAL CONTACTS, AND/OR OTHER YES, LIMITED OYES X YES, UNLIMITED E) □NAME 20. EXISTING COUNTY Ĕ HABS S HAER-1 HAER ON S STATE

Evans, Gail E. H. with T. Allan Comp. Park Service, Pacific Northwest Region. Phone communication with Gail Evans, 17 September. 1983. Historic Resource Study: Olympic National Park. Seattle: National


Stokes, Rich.

22. INVENTORIED BY Leslie Helm/Gail E.H.

Evans

AFFILIATION National Park Service

DATE 9/82, 1984





Description
Coastie Head Cabin; Other
Clallam County, WA; Coastal near Lake Ozette
view looking East























